

CITY OF APPLETON
Department of Public Works
MEMORANDUM

TO: Finance Committee
 Municipal Services Committee
 Utilities Committee

SUBJECT: Award of Contract

The Department of Public Works recommends that the following described work:
Green Parking Ramp Stair Replacement

Be awarded to:

Name: Hietpas Welding, Inc.
Address: 5925 N. Richmond Street
Appleton, WI 54913

In the amount of : 59,266.00
With a 5 % contingency of : \$2,963.30
For a project total not to exceed : \$62,229.30

**** OR ****

In an amount Not To Exceed : _____

Budget: \$65,000.00
Estimate: \$60,000.00
Committee Date: 10/08/14
Council Date: 10/15/14

<u>Item</u>	<u>Description</u>	<u>Qty./</u>	<u>Unit</u>	#1 - Hietpas Welding, Inc. <u>Total/\$</u>	#2 - The Boldt Company <u>Total/\$</u>
1.	Remove and dispose of existing 4"x4"x42" steel angle brace supports (66 pieces total)	1	Lump sum	\$2,700.00	\$10,150.00
2.	Remove and dispose of existing concrete stair treads and painted steel stair pans (74 Total)	1	Lump sum	\$5,980.00	\$20,590.00
3.	Remove and dispose of existing concrete landings and supporting steel panels (size varies at each ramp level - 8 landings total)	1	Lump sum	\$3,700.00	\$15,400.00
4.	Clean and paint (primer only) existing 1" wide angled stair pan stringer supports (148 total)	1	Lump sum	\$1,950.00	\$5,400.00
5.	Furnish and Install new 42" wide 12GA stainless steel stair pans and 2" thick 4000 PSI concrete stair treads including all necessary fabrication, field assembly and welding per attached detail drawings. Concrete treads shall be broom finished and sealed with a clear penetrating sealer (74 pans/treads total)	1	Lump sum	\$23,440.00	\$57,800.00
6.	Furnish and Install new 12GA stainless steel landing pans (size varies at each ramp level) and 4" thick 4000 PSI concrete landings including all necessary fabrication, field assembly and welding per attached Detail Drawings. Concrete shall be broom finished and sealed with a clear penetrating sealer (8 landings total)	1	Lump sum	\$21,496.00	\$26,100.00
TOTAL ITEMS 1 THROUGH 6:				\$59,266.00	\$135,440.00