

**MUNICIPAL SERVICES COMMITTEE – July 9, 2018**  
**Presentation of June 19, 2018 Public Information Session**

**INTRO:**

On June 19, 2018 we conducted Public Information Sessions for:

Winnebago Street	(Division St to Drew St)
Randall Street	(Oneida St to Meade St)

All streets listed above are proposed to undergo a total reconstruction. The projects to reconstruct the above listed streets will include the removal and replacement of all existing asphalt/concrete pavement, curb and gutter, stone base, driveway aprons, and spot removal and replacement of sidewalk, if applicable, within the project limits.

The pavement rating shown is based on the City's pavement rating system with values from 1 to 100 with 100 being the worst.

**WINNEBAGO STREET – Division St to Drew St (2020 Asphalt Pavt Reconstruct)**

**EXISTING CONDITIONS:**

- Pavement rating = 41
- Existing right of way width = 60'
- Existing pavement width:
  - 33' (Division – Appleton)
  - 37' (Appleton – Morrison)
  - 32' (Morrison – Drew)
- Existing Pavement
  - Asphalt 1997
  - Asphalt 1967
  - Concrete curb & gutter 1939, 1947
- Existing Water Main
  - 4" CIP constructed ? (year unknown)
- Existing Sanitary Sewer
  - 8", 10" PVC constructed 1994
- Existing Storm Sewer
  - 12", 18" Con constructed 1937, 1965

**PROPOSED IMPROVEMENTS**

- **Underground utilities to be improved in 2019.**
- **DIVISION ST – APPLETON ST**
  - **New concrete curb & gutter and asphalt pavement – 31' (boc to boc) (2' narrower than existing)**
  - **6 trees in poor condition would be removed**
  - **6 terrace trees would be preserved by narrowing street**
- **APPLETON ST – MORRISON ST**
  - **New concrete curb & gutter and asphalt pavement – 37' (boc to boc) (same as existing)**
    - **Block between Oneida & Morrison to shift 1' to north to save 5 existing terrace trees along south side**
  - **Work with school district to possibly pave terrace area for better drop-off area between Appleton & Oneida (Columbus Elementary)**
  - **Re-establish existing indented paved area adjacent to Zion Lutheran Church**
  - **2 trees to be removed between Oneida & Morrison due to shifting roadway 1' to north**
- **MORRISON ST – DREW ST**
  - **New concrete curb & gutter and asphalt pavement – 31' (boc to boc) (1' narrower than existing)**
  - **6 trees to be removed due to poor condition.**

## **COST ESTIMATES AND ASSESSMENTS**

- **Estimated Construction Cost = \$620,000**

## **PUBLIC MEETING FEEDBACK**

- **55 Properties along project limits, 1 property owner attended the public info meeting**
- **0 questionnaire were returned**
  - **Feedback: wanted to know which trees would be saved across from Zion Lutheran.**