



CONTRACT MODIFICATION
CITY OF APPLETON, WISCONSIN

CHANGE ORDER WRITTEN AMENDMENT MODIFICATION NO 1: 003

TO CONTRACTOR: Staab Construction Corporation

PROJECT: Regulatory Upgrade and Process Improvement PROJECT NO: 468399

OWNER: City of Appleton

ENGINEER: CH2MHILL

The following modification(s) to the Contract are hereby ordered (use additional pages if required):

See RFQ Log attached. Includes RFQs 24, 25 and 27 through 37.

Reason for Modification(s):

Various. See RFQs 24, 25 and 27 through 37 attached.

Attachments (List Supporting Documents):

RFQs 24, 25 and 27 through 37, attached.

Contract Amount or Price		Contract Times (Calculate Days)	
Original	\$4,857,000	Original Duration	<u>365</u> Days
Previous Contract Modification(s) (Add/Deduct)	<u>\$(87,035)</u>	Previous Contract Modification(s) (Add/Deduct)	<u>0</u> Days
This Contract Modification (Deduct)	<u>\$40,029</u>	This Contract Modification (Add/Deduct)	<u>0</u> Days
Revised Contract Amount	<u>\$4,809,994</u>	Revised Contract Time	<u>365</u> Days

The Revised Contract Completion Date is: _____, 20____

Owner	Contractor	Engineer Recommendation ²
By: <u>[Signature]</u>	By: <u>[Signature]</u>	By: <u>Tony Myers</u>
Date: <u>10/9/14</u>	Date: <u>10/8/14</u>	Date: <u>10-07-2014</u>

¹ Number all Modifications consecutively.

Copies: Owner

² Recommendation necessary for Change Orders.

City of Appleton RFQ Log

Regulatory Upgrade and Process Improvement Project

Number	Date Initiated	Description	Comments	Status	Amount
024	7/2/14	Valve Shaft Replacement	Replace corroded valve shaft in clearwell with 316 SST shaft	Accepted	\$ 3,191
025	7/7/14	Electrical Conduit Lime Room	Change from PVC coated to Aluminum in lime areas.	Accepted	\$ (5,972)
026	7/15/14	Polymer Rotometers	Reduce size of rotometers from 20 gpm to 10 gpm. (add \$625)	Rejected	
027	7/23/14	UV Cable Length	Increase length of UV cable to reach equipment	Accepted	\$ 4,304
028	7/28/14	Remove 12" SST Pipe	Remove 12" SST pipe in membrane wet well	Accepted	\$ 1,618
029	8/6/14	Hach WIMS Programming	Cost for Hach WIMS programming services per WCD #1 dated 7/21/14	Accepted	\$ 9,964
030	8/7/14	Expansion Joint Leakage Repair	Water Leakage under walls at the expansion joint	Accepted	\$ 1,541
031	8/15/14	Hub Drains	Eliminate hub drains and drain piping near UV reactors, per RFI 032.	Accepted	\$ (4,773)
032	8/20/14	Vertical Expansion Joints	Install vertical expansion joint in 2 new CT tank walls	Accepted	\$ 12,354
033	8/21/14	Post-UV Chemical Injection Ports	Modify post-UV chemical injection ports as shown in sketches	Accepted	\$ 1,733
034	8/25/14	Repair existing clearwell floor expansion joint	Previously identified repair work Owner would like done in this contract	Accepted	\$ 6,702
035	8/25/14	16" pipe Expansion Joint	Installing a 16" expansion joint in the 16" RTN line	Accepted	\$ 3,175
036	9/5/14	Chemical Table Drip Pan	Add a drip pan to the ammonia chemical feed pump table.	Accepted	\$ 1,338
037	9/19/14	Contact Valve Positioner Wiring	Add electrical wire/conduit for position feature on FTW valves	Accepted	\$ 4,854
		TOTAL	Change Order 3 Processed for RFQs 24, 25 and 27 through 37. Total Cost = Add of \$40,029		\$ 40,029