



Legislation Details (With Text)

**File #:** 22-1455      **Version:** 1      **Name:**  
**Type:** Report Action Item      **Status:** Passed  
**File created:** 11/3/2022      **In control:** Municipal Services Committee  
**On agenda:** 11/7/2022      **Final action:** 11/16/2022

**Title:** Linwood Ave, from College Avenue to Summer Street, be reconstructed with concrete pavement and curb and gutter. The details of the proposed Linwood Avenue reconstruction project are as follows:  
College Ave - Franklin St:  
· New concrete pavement constructed to a width of 34' from back of curb to back of curb, which is 3' narrower than the existing street within this portion of the project.  
· 1 travel lane in each direction  
· Dedicated right turn lane at College Avenue for southbound traffic  
· Dedicated bike lanes along both sides of the street  
· On-street parking to be prohibited along both sides of the street  
Franklin St - Badger Ave:  
· New concrete pavement to be constructed to a width of 33' from back of curb to back of curb, which is 4' narrower than the existing street within this portion of the project.  
· 1 travel lane in each direction  
· Parking lane along east side of street. On-street parking to be prohibited along the west side of the street  
· Traffic Calming elements to be implemented:  
o Linwood & Franklin - narrowing curb lines  
o Linwood & Packard - raised crosswalk  
o Linwood & Winnebago - raised median  
Badger Ave - Summer St:  
· New concrete pavement to be constructed to a width of 24' from back of curb to back of curb, which is 1' narrower than the existing street within this portion of the project.  
· 1 travel lane in each direction  
· On-street parking to be prohibited along both sides of the street

**Sponsors:**

**Indexes:**

**Code sections:**

**Attachments:** 1. Linwood Ave-email.pdf

Date	Ver.	Action By	Action	Result
11/16/2022	1	Common Council	approved	Pass
11/7/2022	1	Municipal Services Committee	recommended for approval	Pass

**Linwood Ave**, from College Avenue to Summer Street, be reconstructed with concrete pavement and curb and gutter. The details of the proposed Linwood Avenue reconstruction project are as follows:

*College Ave - Franklin St:*

- New concrete pavement constructed to a width of 34' from back of curb to back of curb, which is 3' narrower than the existing street within this portion of the project.
- 1 travel lane in each direction

- Dedicated right turn lane at College Avenue for southbound traffic
- Dedicated bike lanes along both sides of the street
- On-street parking to be prohibited along both sides of the street

*Franklin St - Badger Ave:*

- New concrete pavement to be constructed to a width of 33' from back of curb to back of curb, which is 4' narrower than the existing street within this portion of the project.
- 1 travel lane in each direction
- Parking lane along east side of street. On-street parking to be prohibited along the west side of the street
- Traffic Calming elements to be implemented:
  - o Linwood & Franklin - narrowing curb lines
  - o Linwood & Packard - raised crosswalk
  - o Linwood & Winnebago - raised median

*Badger Ave - Summer St:*

- New concrete pavement to be constructed to a width of 24' from back of curb to back of curb, which is 1' narrower than the existing street within this portion of the project.
- 1 travel lane in each direction
- On-street parking to be prohibited along both sides of the street