



Legislation Text

File #: 19-0888, **Version:** 2

R-B-Summer Street, from Gillet Street to Richmond Street, be reconstructed with asphalt and concrete pavement and curb and gutter. The dimensions of the Summer Street reconstruction project are as follows:

Gillet Street-295' west of Mason Street: New asphalt pavement and concrete curb & gutter to be constructed to a width of 31' from back of curb to back of curb, which is 2' narrower than the existing street within this portion of the project.

285' west of Mason Street- Mason Street: New concrete pavement to be constructed to a width of 33' from back of curb to back of curb, which is the same width as the existing street within this portion of the project.

Mason Street- 100' west of Richmond Street: New asphalt pavement and concrete curb & gutter to be constructed to a width of 31' from back of curb to back of curb, which is 2' narrower than the existing street within this portion of the project.

100' west of Richmond Street- Richmond Street: New asphalt pavement and concrete curb & gutter to be constructed to a width of 33' from back of curb to back of curb, which is the same width as the existing street within this portion of the project.

Existing parking provisions within the project limits will remain unchanged.