

City of Appleton

100 North Appleton Street Appleton, WI 54911-4799 www.appleton.org

Legislation Text

File #: 21-1699, Version: 1

Durkee Street, from 200' south of Lawrence Street to Washington Street, be reconstructed with concrete pavement and curb and gutter. The details of the proposed Durkee Street reconstruction project are as follows:

200' south of Lawrence St - Lawrence St:

- New concrete pavement constructed to a width of 38' from back of curb to back of curb, which is the same width as the existing street within this portion of the project.
- New concrete sidewalk extended to the south limits of the project along the east side of the street
- 1 travel lane in each direction
- Parallel on-street parking along both sides of the street
- Proposed streetscape elements per Downtown Streetscape Design Guide
- Cul-de-sac at south end of the block

Lawrence St - College Ave:

- New concrete pavement constructed to a width of 38' from back of curb to back of curb, which is 5' wider than the existing street within this portion of the project.
- 1 travel lane in each direction
- Shared bike lanes
- Parallel on-street parking along both sides of the street
- Proposed streetscape elements per Downtown Streetscape Design Guide

College Ave -Washington St:

- New concrete pavement constructed to a width of 38' from back of curb to back of curb, which is 7' narrower than the existing street within this portion of the project.
- 1 travel lane in each direction
- Shared bike lanes
- Parallel on-street parking along both sides of the street
- Proposed streetscape elements per Downtown Streetscape Design Guide

Fil	e #·	21	-1699	Ver	sion:	1

• 1 marked mid-block crosswalk