



Legislation Details (With Text)

File #: 18-0890 **Version:** 1 **Name:**

Type: Report Action Item **Status:** Passed

File created: 6/7/2018 **In control:** Municipal Services Committee

On agenda: 7/23/2018 **Final action:** 8/1/2018

Title: Henry Street, from Warner Street to Telulah Avenue, be reconstructed with asphalt pavement and concrete curb & gutter. The dimensions of the Henry Street reconstruction project are as follows:
175' west of Warner St - Warner St: New asphalt pavement to be constructed to a width of 29' from back of curb to back of curb, which is the same width as the existing street within this portion of the project.
Warner St - Telulah Ave: New asphalt pavement to be constructed to a width of 33' from back of curb to back of curb, which is the same width as the existing street within this portion of the project. New concrete sidewalk would be constructed along the north side of Henry Street from 175' west of Warner Street to Warner Street, and along the south side of Henry Street from 175' west of Warner Street to Telulah Avenue. Existing parking provisions within the project limits will remain unchanged except near midblock crosswalk.

Sponsors:

Indexes:

Code sections:

Attachments: 1. Sidewalks on Warner & Henry Street.pdf, 2. Letter from 513 S. Telulah Ave.pdf, 3. Photo of Henry Street.pdf

Date	Ver.	Action By	Action	Result
8/1/2018	1	Common Council	approved	Pass
7/23/2018	1	Municipal Services Committee	recommended for approval	Pass
7/9/2018	1	Municipal Services Committee	held	Pass
6/20/2018	1	Common Council	referred	
6/11/2018	1	Municipal Services Committee	recommended for approval	Pass

Henry Street, from Warner Street to Telulah Avenue, be reconstructed with asphalt pavement and concrete curb & gutter. The dimensions of the Henry Street reconstruction project are as follows:

175' west of Warner St - Warner St: New asphalt pavement to be constructed to a width of 29' from back of curb to back of curb, which is the same width as the existing street within this portion of the project.

Warner St - Telulah Ave: New asphalt pavement to be constructed to a width of 33' from back of curb to back of curb, which is the same width as the existing street within this portion of the project.

New concrete sidewalk would be constructed along the north side of Henry Street from 175' west of Warner Street to Warner Street, and ~~along the south side of Henry Street from 175' west of Warner Street to Telulah Avenue.~~ Existing parking provisions within the project limits will remain unchanged **except near midblock crosswalk.**