



Legislation Details

File #: 18-1094 **Version:** 1 **Name:**

Type: Report Action Item **Status:** Passed

File created: 7/18/2018 **In control:** Municipal Services Committee

On agenda: 7/23/2018 **Final action:** 8/1/2018

Title: Winnebago Street, from Division Street to Drew Street, be reconstructed with asphalt pavement and concrete curb & gutter. The dimensions of the Winnebago Street reconstruction project are proposed as follows:
Division Street - Appleton Street: New asphalt pavement and concrete curb & gutter to be constructed to a width of 31' from back of curb to back of curb, which is 2' narrower than the existing street within this portion of the project.
Appleton Street - Oneida Street: New asphalt pavement and concrete curb & gutter to be constructed to a width of 37' from back of curb to back of curb, which is the same width as the existing street within this portion of the project.
Oneida Street - Morrison Street: New asphalt pavement and concrete curb & gutter to be constructed to a width of 37' from back of curb to back of curb, which is the same width as the existing street within this portion of the project. This block would be shifted 1' to the north in order to preserve 5 existing street trees along the south terrace. The existing indented parking area adjacent to the Zion Lutheran Church would be maintained as part of this project.
Morrison Street - Drew Street: New asphalt pavement and concrete curb & gutter to be constructed to a width of 31' from back of curb to back of curb, which is 1' narrower than the existing street within this portion of the project.
Existing parking provisions within the project limits proposed to remain unchanged.

Sponsors:

Indexes:

Code sections:

Attachments:

Date	Ver.	Action By	Action	Result
8/1/2018	1	Common Council	approved	Pass
7/23/2018	1	Municipal Services Committee	recommended for approval	Pass