



Legislation Details (With Text)

File #: 19-0638 **Version:** 1 **Name:**

Type: Report Action Item **Status:** Passed

File created: 5/2/2019 **In control:** Municipal Services Committee

On agenda: 5/6/2019 **Final action:** 5/15/2019

Title: Harris Street, from Badger Avenue to Richmond Street, be reconstructed with asphalt pavement and concrete curb & gutter. The dimensions of the Harris Street reconstruction project are as follows:
Badger Avenue - 200' east of Badger Avenue: New asphalt pavement to be constructed to a width of 37' from back of curb to back of curb, which is 4' wider than the existing street within this portion of the project. The 4' widening will be achieved along the south curb line.

200' east of Badger Avenue - Summit Street: New asphalt pavement to be constructed to a width of 33' from back of curb to back of curb, which is the same width as the existing street within this portion of the project.

Summit Street - Richmond Street: New asphalt pavement to be constructed to a width of 31' from back of curb to back of curb, which is 2' narrower than the existing street within this portion of the project.

Sponsors:

Indexes:

Code sections:

Attachments:

Date	Ver.	Action By	Action	Result
5/15/2019	1	Common Council	approved	Pass
5/6/2019	1	Municipal Services Committee	recommended for approval	Pass

Harris Street, from Badger Avenue to Richmond Street, be reconstructed with asphalt pavement and concrete curb & gutter. The dimensions of the Harris Street reconstruction project are as follows:

Badger Avenue - 200' east of Badger Avenue: New asphalt pavement to be constructed to a width of 37' from back of curb to back of curb, which is 4' wider than the existing street within this portion of the project. The 4' widening will be achieved along the south curb line.

200' east of Badger Avenue - Summit Street: New asphalt pavement to be constructed to a width of 33' from back of curb to back of curb, which is the same width as the existing street within this portion of the project.

Summit Street - Richmond Street: New asphalt pavement to be constructed to a width of 31' from back of curb to back of curb, which is 2' narrower than the existing street within this portion of the project.