



Legislation Details (With Text)

File #:	22-1455	Version:	1	Name:	
Type:	Report Action Item	Status:		Passed	
File created:	11/3/2022	In control:		Municipal Services Committee	
On agenda:	11/7/2022	Final action:		11/16/2022	
Title:	<p>Linwood Ave, from College Avenue to Summer Street, be reconstructed with concrete pavement and curb and gutter. The details of the proposed Linwood Avenue reconstruction project are as follows:</p> <p>College Ave - Franklin St:</p> <ul style="list-style-type: none">· New concrete pavement constructed to a width of 34' from back of curb to back of curb, which is 3' narrower than the existing street within this portion of the project.· 1 travel lane in each direction· Dedicated right turn lane at College Avenue for southbound traffic· Dedicated bike lanes along both sides of the street· On-street parking to be prohibited along both sides of the street <p>Franklin St - Badger Ave:</p> <ul style="list-style-type: none">· New concrete pavement to be constructed to a width of 33' from back of curb to back of curb, which is 4' narrower than the existing street within this portion of the project.· 1 travel lane in each direction· Parking lane along east side of street. On-street parking to be prohibited along the west side of the street· Traffic Calming elements to be implemented:<ul style="list-style-type: none">o Linwood & Franklin - narrowing curb lineso Linwood & Packard - raised crosswalko Linwood & Winnebago - raised median <p>Badger Ave - Summer St:</p> <ul style="list-style-type: none">· New concrete pavement to be constructed to a width of 24' from back of curb to back of curb, which is 1' narrower than the existing street within this portion of the project.· 1 travel lane in each direction· On-street parking to be prohibited along both sides of the street				
Sponsors:					
Indexes:					
Code sections:					
Attachments:	1. Linwood Ave-email.pdf				

Date	Ver.	Action By	Action	Result
11/16/2022	1	Common Council	approved	Pass
11/7/2022	1	Municipal Services Committee	recommended for approval	Pass

Linwood Ave, from College Avenue to Summer Street, be reconstructed with concrete pavement and curb and gutter. The details of the proposed Linwood Avenue reconstruction project are as follows:

College Ave - Franklin St:

- New concrete pavement constructed to a width of 34' from back of curb to back of curb, which is 3' narrower than the existing street within this portion of the project.
- 1 travel lane in each direction

- Dedicated right turn lane at College Avenue for southbound traffic
- Dedicated bike lanes along both sides of the street
- On-street parking to be prohibited along both sides of the street

Franklin St - Badger Ave:

- New concrete pavement to be constructed to a width of 33' from back of curb to back of curb, which is 4' narrower than the existing street within this portion of the project.
- 1 travel lane in each direction
- Parking lane along east side of street. On-street parking to be prohibited along the west side of the street
- Traffic Calming elements to be implemented:
 - o Linwood & Franklin - narrowing curb lines
 - o Linwood & Packard - raised crosswalk
 - o Linwood & Winnebago - raised median

Badger Ave - Summer St:

- New concrete pavement to be constructed to a width of 24' from back of curb to back of curb, which is 1' narrower than the existing street within this portion of the project.
- 1 travel lane in each direction
- On-street parking to be prohibited along both sides of the street